

Please scan to verify the report



Page 1 of 17

No: PMC20250305001

## TEST REPORT

NAME OF  
SAMPLE:

Air Conditioner

APPLICANT:

TCL Air Conditioner (Zhongshan) Co., Ltd.

CLASSIFICATION OF  
TEST:

Commission Test


**Testing Center of TCL Air Conditioner (Zhongshan) Co., Ltd.**

59 Nantou Road West, Nantou, Zhongshan, Guangdong, China



# TEST REPORT

## The rating and performance tests for Air-conditioner

Applicant Name .....	TCL Air Conditioner (Zhongshan) Co., Ltd.		
Address .....	59 Nantou Road West, Nantou, Zhongshan, Guangdong, China		
Manufacturer .....	TCL Air Conditioner (Zhongshan) Co., Ltd.		
Address .....	59 Nantou Road West, Nantou, Zhongshan, Guangdong, China		
Factory .....	Same as applicant		
Product name .....	Air conditioner		
Trademark .....	TCL		
Model / type reference .....	TAC-24COSAI/XA31T		
Rating and characteristics. ....	220-240V~ ,50/60Hz		
Date of receipt of test item	2025-03-05	Date(s) of test	2025-03-05
Test specification/Standard .....	SASO 2663/2021 SASO GSO ISO 5151: 2017 ISO 16358-1 :2013/Cor 1 :2013/AMD1 :2019		
To compile .....	李林海		
audit .....	林艺鸣		
The director of the approval	赖福远		
Date of issue .....	2025-03-06		

This report is for the exclusive use of **TCL**'s Client and is provided pursuant to the agreement between **TCL** and its Client. **TCL** 's responsibility and liability are limited to the terms and conditions of the agreement. **TCL** assumes no liability to any party, other than to the Client in accordance with the agreement, for any loss, expense or damage occasioned by the use of this report. Only the Client is authorized to permit copying or distribution of this report and then only in its entirety. Any use of the **TCL** name or one of its marks for the sale or advertisement of the tested material, product or service must first be approved in writing by **TCL**. This test report relates only to the tested product, and shall not be reproduced except in full, without written approval of **TCL**.

This report by itself does not imply that the material, product, or service is or has ever been under an **TCL** certification program.

To check the authenticity of the test reports and certification. please pay attention to **TCL** digital signature with blue banner at the top of the test report.

If **TCL** digital signature could not be displayed, please get access to the website <http://hao.tcl.com/report>, to verify that the report of authenticity.



### The rating and performance tests for Air conditioner

Test case verdicts	/
Test case does not apply to the test object	N.A.
Test item does meet the requirement	Pass
Test item does not meet the requirement	N.A.
Procedure deviation	N.A.
Non-standard test method	N.A.

#### General remarks

The test results presented in this report relate only to the item tested.

The test report is invalid without the official stamp of TCL.

The test report is invalid without the signatures of Author and Reviewer.

#### Test Method

T1: Within the first 3 minutes after the indoor unit is powered on, start up and run the cooling mode, set the temperature of 30℃, medium speed wind, press the ECO or Sleep button 7 times continuously within 8 seconds, and the buzzer beeps 3 times, then set 26℃;

T3: Within the first 3 minutes after the indoor unit is powered on, start up and run the cooling mode, set the temperature of 30℃, medium speed wind, press the ECO or Sleep button 7 times continuously within 8 seconds, and the buzzer beeps 3 times, then set 28℃;

Half capacity: Within the first 3 minutes after the indoor unit is powered on, start up and run the cooling mode, set the temperature of 30℃, medium speed wind, press the ECO or Sleep button 7 times continuously within 8 seconds, and the buzzer beeps 3 times, then set 27℃;

T1 minimum capacity: Within the first 3 minutes after the indoor unit is powered on, start up and run the cooling mode, set the temperature of 30℃, medium speed wind, press the ECO or Sleep button 7 times continuously within 8 seconds, and the buzzer beeps 3 times, then set 31℃;

(Note: If you do not clearly hear the three short beeps of the buzzer, please power off and operate again)




Brief description of the tested sample(s)		
1	Ratings	
	Rated voltage/rated voltage range (V)	220-240
	Rated frequency (Hz)	50/60
	Rated input (W)	Cooling (T1- Full load capacity) : 1875 Cooling (T1- Half load capacity) : 653 Cooling (T3) : 2298 Cooling (T1- Minimum load capacity) : 367 Heating : /
	Rated capacity (Btu/h)	Cooling (T1- Full load capacity) : 22500 Cooling (T1- Half load capacity) : 10700 Cooling (T3) : 20800 Cooling (T1- Minimum load capacity) : 6200 Heating : /
	Rated current (A)	/
2	Type of power supply	<input checked="" type="checkbox"/> Single phase <input type="checkbox"/> Three phase
3	Construction of the unit	<input checked="" type="checkbox"/> Split type <input type="checkbox"/> Single packaged type <input type="checkbox"/> Multi-split type
4	Type of the unit considering if it has the air ducts (A/C Configuration— Air Distribution)	<input type="checkbox"/> Spot <input type="checkbox"/> Single-duct <input type="checkbox"/> Double ducts <input checked="" type="checkbox"/> Non Ducted
5	The number of the indoor units if multi-split type	
6	Type of the indoor unit if split type	<input checked="" type="checkbox"/> Wall-mounted <input type="checkbox"/> Free-standing <input type="checkbox"/> Ceiling-mounted <input type="checkbox"/> Other type
7	Type of outdoor unit if split type	<input checked="" type="checkbox"/> Free-standing <input type="checkbox"/> Other type
9	Supplementary heating element	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
10	Operation function	<input type="checkbox"/> Cooling mode and heating mode <input checked="" type="checkbox"/> Cooling only <input type="checkbox"/> Heating only
11	Type of the refrigerant	As attach page
12	Mass of refrigerant (kg)	As attach page
13	Compressor information	As attach page
14	Compressor stages type	<input type="checkbox"/> Fixed capacity unit <input type="checkbox"/> Two-stage capacity unit <input type="checkbox"/> Multi-stage capacity unit <input checked="" type="checkbox"/> Variable capacity unit



## Photo of nameplate:



**Photo of the tested sample:**



## Photo of compressor:





**Summary**

Test method		Enthalpy test room
COOLING CAPACITY(T1-Full load capacity)	Total cooling capacity in Btu/h	23812
	Air conditioner power consumption in W	1826
	Energy Efficiency Ratio(EER) in Btu/h/w	13.04
COOLING CAPACITY(T1-Half load capacity)	Total cooling capacity in W	11420
	Air conditioner power consumption in W	639
	Energy Efficiency Ratio(EER)	17.87
COOLING CAPACITY(T3)	Total cooling capacity in Btu/h	21496
	Air conditioner power consumption in W	2434
	Energy Efficiency Ratio(EER) in Btu/h/w	9.57
COOLING CAPACITY(T1-Minimum load capacity)	Total cooling capacity in W	6616
	Air conditioner power consumption in W	359
	Energy Efficiency Ratio(EER) in Btu/h/w	18.43
HEATING CAPACITY	Total cooling capacity in w	/
	Air conditioner power consumption in W	/
	Energy Efficiency Ratio(COP) in w/w	/

**Test Result:**
☒ **Pass**
☐ **Fail**

**Note:** If failed, it shall be indicated which part it was fail in.





## 1- Sample Information

Brand	TCL			
Model No.	System (if application)	KT3F-58GW/YXABp(E/6)(080944)		
	Indoor (split system only)	/		
	Outdoor (split system only)	/		
Serial number	Indoor: G440N02001N124121301		Outdoor: G440W02001N124121302	
Air-Conditioner Type	Split air conditioner			
Air Distribution	Four way			
Type of system	R410A	Mass of Refrigerant (kg)	1.10	
Heat transfer	Cooling only			
Voltage(V)	220-240			
Phase	1ph			
Hz	50/60			
Compressor	Type	Hermetic motor-compressor		
	Brand	Sanyo		
	Model Name	C-6RZ180H3BAF		
	Maker	AVIC ELECTROMECHANICAL(SHENYANG)SANYO O REFRIGERATION EQUIPMENT CO.,LTD.		
	Country of Origin	China		
Indoor Fan motor	Type	DC motor		
	Brand	WELLING		
	Model	ZKFP-45-8-184L		
	Maker	GUANGDONG WELLING MOTOR MANUFACTURING CO.,LTD.		
	Country of Origin	China		
Outdoor Fan motor	Type	DC motor		
	Brand	Wolong		
	Model	WZD-A02085L-01TL		
	Maker	Wolong Electric (Ji nan) Motor Co.,Ltd.		
	Country of Origin	China		
Evaporator	Volume(mm)	896mm x 399mm x 25.4 mm		
	Type	Hydrophilic & Louver Fin; Innergroover tube type		
Condenser	Volume(mm)	858 mm x 663 mm x 23.2 mm		
	Type	Louver or Corrugated Fin; Innergroover tube type		
Refrigerant	Type: R410A	1100g		
Dimensions	Indoor(mm)	Width:1191	Depth :360	Height :258
	Outdoor(mm)	Width :920	Depth :380	Height :699



## 2- Test report

## 2.1 Cooling capacity test (T1-Full load capacity)

Data to be recorded for Enthalpy cooling capacity tests

Test Duration(min)	90
Power supplied	220-240V
Applied voltage (V)	229.0
Frequency (Hz)	60
Current (A)	8.337
Power Consumption (W)	1826
Power factor	95.7%
Fan speed settings	High speed
Dry bulb temperature, indoor (°C)	26.99
Wet bulb temperature, indoor (°C)	19.01
Dry bulb temperature, outdoor (°C)	34.99
Wet bulb temperature, outdoor (°C)	24.00
Barometer (Pa)	102.27
Indoor cooling capacity (Btu/h)	23812
Sensible cooling capacity(Btu/h)	22502
Latent cooling capacity (dehumidifying capacity) (Btu/h)	1310
Static pressure(Pa)	0.0
Volume flow rate of air(m3/hr)	1809.1
Cooling capacity (Btu/h)	23812
EER(Btu/h)/W	13.04



## 2.2 Cooling capacity test (T1-Half load capacity)

Test Duration(min)	90
Power supplied	220-240V
Applied voltage (V)	229.5
Frequency (Hz)	60
Current (A)	4.254
Power Consumption (W)	639
Power factor	65.5%
Fan speed settings	High speed
Dry bulb temperature, indoor (°C)	27.00
Wet bulb temperature, indoor (°C)	19.00
Dry bulb temperature, outdoor (°C)	35.02
Wet bulb temperature, outdoor (°C)	24.00
Barometer (Pa)	102.41
Indoor cooling capacity (Btu/h)	11420
Sensible cooling capacity (Btu/h)	11079
Latent cooling capacity (dehumidifying capacity) (W)	341
Static pressure(Pa)	0.0
Volume flow rate of air(m3/hr)	1604.1
Cooling capacity (Btu/h)	11420
EER(Btu/h)/W	17.87



## 2.3 Test record of cooling capacity test (T3)

Test Duration(min)	90
Power supplied	220-240V
Applied voltage (V)	229.9
Frequency (Hz)	60
Current (A)	10.09
Power Consumption (W)	2247
Power factor	96.9%
Fan speed settings	High speed
Dry bulb temperature, indoor (°C)	28.98
Wet bulb temperature, indoor (°C)	18.98
Dry bulb temperature, outdoor (°C)	45.98
Wet bulb temperature, outdoor (°C)	23.99
Barometer (Pa)	102.41
Indoor cooling capacity (Btu/h)	21496
Sensible cooling capacity(Btu/h)	21407
Latent cooling capacity (dehumidifying capacity) (Btu/h)	89
Static pressure(Pa)	0.0
Volume flow rate of air(m3/hr)	1806.4
Cooling capacity (Btu/h)	21496
EER(Btu/h)/W	9.57



## 2.4 Test record of cooling capacity test (T1- Minimum load capacity)

Test Duration(min)	90
Power supplied	220-240V
Applied voltage (V)	229.9
Frequency (Hz)	60
Current (A)	2.641
Power Consumption (W)	359
Power factor	59.1%
Fan speed settings	High speed
Dry bulb temperature, indoor (°C)	26.99
Wet bulb temperature, indoor (°C)	18.99
Dry bulb temperature, outdoor (°C)	35.00
Wet bulb temperature, outdoor (°C)	24.00
Barometer (Pa)	102.22
Indoor cooling capacity (Btu/h)	1939
Sensible cooling capacity(Btu/h)	1880
Latent cooling capacity (dehumidifying capacity) (Btu/h)	59
Static pressure(Pa)	0.0
Volume flow rate of air(m3/hr)	1074.2
Cooling capacity (Btu/h)	6616
EER(Btu/h)/W	18.43



## 2.5 Test record of heating capacity test (H1)

Test Duration(min)	/
Power supplied	/
Applied voltage (V)	/
Frequency (Hz)	/
Current (A)	/
Power Consumption (W)	/
Power factor	/
Fan speed settings	/
Dry bulb temperature, indoor (°C)	/
Wet bulb temperature, indoor (°C)	/
Dry bulb temperature, outdoor (°C)	/
Wet bulb temperature, outdoor (°C)	/
Barometer (Pa)	/
Indoor heating capacity (W)	/
Sensible heating g capacity (W)	/
Latent heating capacity (dehumidifying capacity) (W)	/
Static pressure(Pa)	/
Volume flow rate of air(m3/hr)	/
heating capacity W	/
heating capacity (Btu/h)	/
COP (Btu/h)/W	/



## 2.5 Functional Performance –Cooling&amp;Heating

Operability at Maximum cooling conditions at 52℃	<input checked="" type="checkbox"/> Tested <input type="checkbox"/> Declared	Result:	<input checked="" type="checkbox"/> Pass <input type="checkbox"/> Fail <input type="checkbox"/> Non Relevant
Operability at Minimum cooling conditions	<input checked="" type="checkbox"/> Tested <input type="checkbox"/> Declared		<input type="checkbox"/> Pass <input type="checkbox"/> Fail <input checked="" type="checkbox"/> Non Relevant
Freeze up air blockage and freeze-up drip	<input checked="" type="checkbox"/> Tested <input type="checkbox"/> Declared		<input checked="" type="checkbox"/> Pass <input type="checkbox"/> Fail <input type="checkbox"/> Non Relevant
Condensate control and enclosure sweat performance	<input checked="" type="checkbox"/> Tested <input type="checkbox"/> Declared		<input checked="" type="checkbox"/> Pass <input type="checkbox"/> Fail <input type="checkbox"/> Non Relevant
Operability at Maximum heating conditions	<input checked="" type="checkbox"/> Tested <input type="checkbox"/> Declared		<input type="checkbox"/> Pass <input type="checkbox"/> Fail <input checked="" type="checkbox"/> Non Relevant
Operability at Minimum heating conditions	<input checked="" type="checkbox"/> Tested <input type="checkbox"/> Declared		<input type="checkbox"/> Pass <input type="checkbox"/> Fail <input checked="" type="checkbox"/> Non Relevant
Verification of automatic defrost	<input checked="" type="checkbox"/> Tested <input type="checkbox"/> Declared		<input type="checkbox"/> Pass <input type="checkbox"/> Fail <input checked="" type="checkbox"/> Non Relevant

2.6 Capacity tests at below condition were considered in this report.

Mode	Indoor air temperature		Outdoor air temperature		Test voltage
	Dry bulb	Wet bulb	Dry bulb	Wet bulb	
Cooling mode (T1-Full load capacity)	27	19	35	24	230V, 60Hz
Cooling mode (T1-Half load capacity)	27	19	35	24	230V, 60Hz
Cooling mode (T3)	29	19	46	24	230V, 60Hz
Cooling mode (T1-Minimum load capacity)	27	19	35	24	230V, 60Hz





**Conclusion**

<b>Cooling capacity test (for condition T1- Full load capacity)</b>					
Mode	Rated	Tested	Verifying	Required EER	Verdict
Cooling capacity, Btu/h	22500	23812	5.83%	$\geq 21375$	Pass
Cooling power input, W	1875	1826	-2.61%	$\leq 1969$	Pass
EER, Btu/W ·h	12.00	13.04	8.67%	$\geq 11.80$	Pass
<b>Cooling capacity test (for condition T1- Half load capacity)</b>					
Cooling capacity, Btu/h	10700	11420	6.73%	$\geq 10165$	Pass
Cooling power input, W	653	639	-2.14%	$\leq 686$	Pass
EER, Btu/W ·h	16.39	17.87	9.03%	$\geq 15.57$	Pass
<b>Cooling capacity test (for condition T3)</b>					
Cooling capacity, Btu/h	20800	21496	3.35%	$\geq 19760$	Pass
Cooling power input, W	2298	2247	-2.22%	$\leq 2413$	Pass
EER, Btu/W ·h	9.05	9.57	5.75%	$\geq 8.30$	Pass
<b>Cooling capacity test (for condition T1- Minimum load capacity)</b>					
Cooling capacity, Btu/h	6200	6616	6.71%	$\geq 5890$	Pass
Cooling power input, W	367	359	-2.18%	$\leq 385$	Pass
EER, Btu/W ·h	16.89	18.43	9.12%	$\geq 16.05$	Pass
<b>Heating capacity</b>					
Heating capacity, W	/	/	/	/	/
Heating power input,	/	/	/	/	/
COP, WW	/	/	/	/	/
CSEC (Kwh/Y):	5504				
<b>Energy class:</b> (base on rated EER at T1)	D				
SEER class	B				
SEER	15.00				



- a) Tested power at full load operation at (T1 and T3) .....  $\leq 1.05 \times$  rated power at full load operation at (T1 and T3).
- b) Tested power at half load operation at (T1) .....  $\leq 1.05 \times$  rated power at half load operation at (T1).
- c) Tested power at minimum load operation at (T1) .....  $\leq 1.05 \times$  rated power at minimum load operation at (T1).
- d) Tested cooling capacity at full load operation at (T1 and T3) .....  $\geq 0.95 \times$  rated cooling capacity at full load operation at (T1 and T3).
- e) Tested cooling capacity at half load operation at (T1) .....  $\geq 0.95 \times$  rated cooling capacity at half load operation at (T1).
- f) Tested cooling capacity at minimum load operation at (T1) .....  $\geq 0.95 \times$  rated cooling capacity at minimum load operation at (T1).
- g) Tested EER at full load operation at (T1 and T3) .....  $\geq$  MEPS and  $\geq 0.95 \times$  rated EER at full load operation (T1 and T3).
- h) Tested power at (H1) .....  $\leq 1.05 \times$  rated power at (H1).
- i) Tested heating capacity at (H1) .....  $\geq 0.95 \times$  rated heating capacity at (H1).
- j) Tested COP .....  $\geq 0.95 \times$  rated COP.
- k) Rated COP (Electrical Resistance) .....  $\leq 1.0$  (W/W).
- l) Tested voltage ..... (refer to the standard mentioned in Clause 2).
- m) Tested Frequency ..... 60 Hz  $\pm 2\%$ .

### Nergy Rating Classification

Table 6 – Seasonal Energy Efficiency Ratio (SEER) Classification

Bar color	Energy class		SEER limits (Btu/W.h)
Dark green	1	A	SEER $\geq 18.0$
Green	2	B	18.0 > SEER $\geq 15.0$
Light green	3	C	15.0 > SEER $\geq 12.5$
Yellow	4	D	12.5 > SEER $\geq 10.0$
Orange	5	E	10.0 > SEER $\geq 9.0$
Red	6	F	9.0 > SEER $\geq 8.0$
Dark Red	7	G	8.0 > SEER

